

# EMC TEST REPORT

On Behalf of

Product Name: Cable Cutting and Stripping Machine

Trademark: N/A

Model Number: TR-880H ( See next page for details)

Prepared For: Dongguan Turing Automation Technology Co., Ltd

Address: 7th Floor, Building C, Beitang Industrial Park, No. 80, Tangxia Section,  
Qingzhang Road, Tangxia Town, Dongguan City, Guangdong  
Province, China, 523710

Prepared By: Shenzhen Huaxiang Testing Co., Ltd

Address: 201, Building A10, Fuhai Information Port, Fuhai Street, Bao'an District,  
Shenzhen City

Report No.: HUAX240627001KR

## Model (S)

TR-QD15, TR-416, TR-5F, TR-340, TR-330, TR-310, TR-4F+Y, TR-416, TR-350, TR-310N, TR-310A, TR-120W, TR-4FN+Y, TR-3FN+Y, TR-4FN, TR-305, TR-201, TR-DZ200, TR-DZ100X, TR-B745, TR-DZ150A, TR-620, TR-640, TR-820, TR-3FN, TR-315Z, TR-660, TR-3FA, TR-3FN+O, TR-3FN+Y+O, TR-4F, TR-315, TR-3F1, TR-3F, TR-19, TR-5806, TR-6806D, TR-8608, TR-8608D, TR-3515, TR-4520, TR-4520S, TR-5010, TR-300, TR-500, TR-1200, TR-3520, TR-2515, TR-6010, TR-2520, TR-8018, TR-7006, TR-A0706, TR-2310, TR-2315, TR-252, TR-3530, TR-4520, TR-4520S, TR-5010, TR-JE2-N, TR-MAX2-S95, TR-508 MAX4, TR-YHT4, TR-SDB2-S, TR-MAX2-ST50, TR-MAX2-S70, TR-MAX1-8S, TR-MAX1-8N, TR-MAX1-6S, TR-MAX1-6N, TR-MAX1-4N, TR-MAX1-4S, MAX2-ST50, MAX2-ST70, TR-HT2-S, TR-MAX3-S150, TR-HT2-6S, TR-C-N, TR-JE2-S, TR-C03, TR-PX2, TR-JE-S, TR-YHT3, TR-YHT2, TR-SDB2-N, TR-SDB2-S, TR-SDB-N, TR-SDB-S, TR-SD-S, TR-SD-N, TR-NX2-S, TR-NX2-N, TR-MAX2 TR-MAX1-6SP TR-JE-N, TR-HT2-N, TR-E-S, TR-E-N, TR-BHT2-N, TR-QG-4S, TR508-16ZW, TR508-25ZW, TR-835F, TR-8030H, TR-810N, TR-870F, TR-850F, TR-503N, TR-810NP, TR-8030YJP, TR-8030HYJS, TR-8030, TR-8120P, TR-816F, TR-8030HYJ, TR-8120, TR-8030HYJN, TR-8010, TR-8030Y, TR-820N, TR-820F, TR-820D, TR-810P, TR-9935, TR-8030Z, TR-C02, TR-840C, TR-C4, TR-C01, TR-BX200, TR-3500BJ, TR-NX11, TR-7006, TR-8400X, TR-9600, TR-9615, TR-9800, TR-9935, TR-880, TR-880L, TR-880XL, TR-880XXL, TR-8008, TR-400F, TR-400XL, TR-880D, TR-880T, TR-808, TR-881XXL, TR-500F, TR-810C, TR-820C, TR-840C, TR-820D, TR-820F, TR-816F, TR-825F, TR-895F, TR-820N, TR-820NP, TR-810NJ, TR-870N, TR-CR8-35S, TR-CR20-55S, TR-CR8-35Z, TR-CR20-25Z, TR-BD028, TR-BD030L, TR-BD032L, TR-BD033S, TR-BD036S, TR-8030, TR-8030G, TR-8030YJ, TR-8030HYJN, TR-8050, TR-8150, TR-8150Q, TR-8240, TR-8300, TR-8300X, TR-F380, TR-F680, TR-FL85, TR-F815, TR-8030X, TR-8010, TR-8010H, TR-F810, TR-9800, TR-9600S, TR-9615, TR-EVA, TR-200MS, TR-120XL, TR-201MS, TR-200LR, TR-700L, TR-400L, TR-121LXZ, TR-200XZ, TR-120R, TR-120LDB, TR-120RDK, TR-120L, TR-120LZH, TR-120LRS, TR-300, TR-L170, TR-LH120, TR-200, TR-LH200, TR-120LR, TR-400L, TR-600

## TABLE OF CONTENT

### Test Report Description

|                                                               |           |
|---------------------------------------------------------------|-----------|
| <b>1. GENERAL INFORMATION .....</b>                           | <b>6</b>  |
| 1.1. Description of Device (EUT) .....                        | 6         |
| 1.2. Test Standards .....                                     | 6         |
| 1.3. Test Summary .....                                       | 7         |
| 1.4. Test Methodology .....                                   | 8         |
| 1.5. Test Facility .....                                      | 8         |
| 1.6. Measurement Uncertainty .....                            | 8         |
| <b>2. MEASURING DEVICE AND TEST EQUIPMENT .....</b>           | <b>9</b>  |
| 2.1. For Power Line Conducted Emission .....                  | 9         |
| 2.2. For Radiated Emission Measurement .....                  | 9         |
| 2.3. For Harmonic Current / Flicker Measurement .....         | 9         |
| 2.4. For Electrostatic Discharge Immunity Test .....          | 9         |
| 2.5. For Electrical Fast Transient /Burst Immunity Test ..... | 10        |
| 2.6. For Surge Immunity Test .....                            | 10        |
| 2.7. For Injected Current Susceptibility Test .....           | 10        |
| 2.8. For Magnetic Field Immunity Test .....                   | 10        |
| 2.9. For Voltage Dips and Interruptions Test .....            | 10        |
| <b>3. POWER LINE CONDUCTED EMISSION MEASUREMENT .....</b>     | <b>11</b> |
| 3.1. Block Diagram of Test Setup .....                        | 11        |
| 3.2. Measuring Standard .....                                 | 11        |
| 3.3. EUT Configuration on Measurement .....                   | 11        |
| 3.4. Operating Condition of EUT .....                         | 12        |
| 3.5. Test Procedure .....                                     | 12        |
| 3.6. Measuring Results .....                                  | 12        |
| <b>4. RADIATED EMISSION MEASUREMENT .....</b>                 | <b>15</b> |
| 4.1. Block Diagram of Test .....                              | 15        |
| 4.2. Measuring Standard .....                                 | 15        |
| 4.3. Radiated Emission Limits .....                           | 15        |
| 4.4. EUT Configuration on Test .....                          | 15        |
| 4.5. Operating Condition of EUT .....                         | 16        |
| 4.6. Test Procedure .....                                     | 16        |
| 4.7. Measuring Results .....                                  | 16        |
| <b>5. HARMONIC CURRENT EMISSION MEASUREMENT .....</b>         | <b>19</b> |
| 5.1. Block Diagram of Test Setup .....                        | 19        |
| 5.2. Measuring Standard .....                                 | 19        |
| 5.3. Operation Condition of EUT .....                         | 19        |
| 5.4. Measuring Results .....                                  | 19        |
| <b>6. VOLTAGE FLUCTUATION AND FLICKER MEASUREMENT .....</b>   | <b>20</b> |
| 6.1. Block Diagram of Test Setup .....                        | 20        |
| 6.2. Measuring Standard .....                                 | 20        |
| 6.3. Operation Condition of EUT .....                         | 20        |
| 6.4. Measuring Results .....                                  | 20        |
| <b>7. ELECTROSTATIC DISCHARGE IMMUNITY TEST .....</b>         | <b>22</b> |
| 7.1. Block Diagram of Test Setup .....                        | 22        |
| 7.2. Test Standard .....                                      | 22        |
| 7.3. Severity Levels and Performance Criterion .....          | 22        |
| 7.4. EUT Configuration .....                                  | 22        |
| 7.5. Operating Condition of EUT .....                         | 23        |
| 7.6. Test Procedure .....                                     | 23        |

|                                                               |           |
|---------------------------------------------------------------|-----------|
| 7.7. Test Results .....                                       | 23        |
| <b>8. RF FIELD STRENGTH SUSCEPTIBILITY TEST .....</b>         | <b>25</b> |
| 8.1. Block Diagram of Test .....                              | 25        |
| 8.2. Test Standard .....                                      | 25        |
| 8.3. Severity Levels and Performance Criterion .....          | 26        |
| 8.4. EUT Configuration on Test .....                          | 26        |
| 8.5. Operating Condition of EUT .....                         | 26        |
| 8.6. Test Procedure .....                                     | 26        |
| 8.7. Test Results .....                                       | 26        |
| <b>9. ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST .....</b> | <b>28</b> |
| 9.1. Block Diagram of Test Setup .....                        | 28        |
| 9.2. Test Standard .....                                      | 28        |
| 9.3. Severity Levels and Performance Criterion .....          | 28        |
| 9.4. EUT Configuration .....                                  | 29        |
| 9.5. Operating Condition of EUT .....                         | 29        |
| 9.6. Test Procedure .....                                     | 29        |
| 9.7. Test Result .....                                        | 29        |
| <b>10. SURGE IMMUNITY TEST .....</b>                          | <b>31</b> |
| 10.1. Block Diagram of Test Setup .....                       | 31        |
| 10.2. Test Standard .....                                     | 31        |
| 10.3. Severity Levels and Performance Criterion .....         | 31        |
| 10.4. EUT Configuration .....                                 | 32        |
| 10.5. Operating Condition of EUT .....                        | 32        |
| 10.6. Test Procedure .....                                    | 32        |
| 10.7. Test Result .....                                       | 32        |
| <b>11. INJECTED CURRENTS SUSCEPTIBILITY TEST .....</b>        | <b>34</b> |
| 11.1. Block Diagram of Test Setup .....                       | 34        |
| 11.2. Test Standard .....                                     | 34        |
| 11.3. Severity Levels and Performance Criterion .....         | 34        |
| 11.4. EUT Configuration .....                                 | 35        |
| 11.5. Operating Condition of EUT .....                        | 35        |
| 11.6. Test Procedure .....                                    | 35        |
| 11.7. Test Results .....                                      | 35        |
| <b>12. MAGNETIC FIELD SUSCEPTIBILITY TEST .....</b>           | <b>37</b> |
| 12.1. Block Diagram of Test .....                             | 37        |
| 12.2. Test Standard .....                                     | 37        |
| 12.3. Severity Levels and Performance Criterion .....         | 37        |
| 12.4. EUT Configuration on Test .....                         | 37        |
| 12.5. Test Procedure .....                                    | 38        |
| 12.6. Test Results .....                                      | 38        |
| <b>13. VOLTAGE DIPS AND INTERRUPTIONS TEST .....</b>          | <b>40</b> |
| 13.1. Block Diagram of Test Setup .....                       | 40        |
| 13.2. Test Standard .....                                     | 40        |
| 13.3. Severity Levels and Performance Criterion .....         | 40        |
| 13.4. EUT Configuration .....                                 | 41        |
| 13.5. Operating Condition of EUT .....                        | 41        |
| 13.6. Test Procedure .....                                    | 41        |
| 13.7. Test Result .....                                       | 41        |
| <b>APPENDIX I (Photos of EUT)</b>                             |           |

## TEST REPORT DECLARATION

|                   |   |                                                                                                                                                         |
|-------------------|---|---------------------------------------------------------------------------------------------------------------------------------------------------------|
| Applicant         | : | <b>Dongguan Turing Automation Technology Co., Ltd</b>                                                                                                   |
| Address :         | : | 7th Floor, Building C, Beitang Industrial Park, No. 80, Tangxia Section, Qingzhang Road, Tangxia Town, Dongguan City, Guangdong Province, China, 523710 |
| Manufacturer:     | : | <b>Turing</b>                                                                                                                                           |
| Address :         | : | 7th Floor, Building C, Beitang Industrial Park, No. 80, Tangxia Section, Qingzhang Road, Tangxia Town, Dongguan City, Guangdong Province, China, 523710 |
| EUT Description : | : | <b>Cable Cutting and Stripping Machine</b>                                                                                                              |
| Model Number      | : | <b>TR-880H</b>                                                                                                                                          |
| Rating(s)         | : | AC 110-220V, 50/60Hz,                                                                                                                                   |
| Test Date         | : | Jun. 26, 2024 - Jul. 02, 2024                                                                                                                           |
| Date of Report    | : | Jul. 02, 2024                                                                                                                                           |

Test Standards:

**EN IEC 61000-6-3: 2021**  
**EN IEC 61000-6-1: 2019**  
**EN IEC 61000-3-2: 2019+A1:2021**  
**EN 61000-3-3: 2013+A2:2021**

The EUT described above is tested by Huaxiang Testing Co., Ltd. EMC Laboratory to determine the maximum emissions from the EUT and ensure the EUT to be compliance with the immunity requirements of the EUT. Shenzhen Huaxiang Testing Co., Ltd. is assumed full responsibility for the accuracy of the test results. Also, this report shows that the EUT technically complies with the 2014/30/EU directive and its amendment requirements.


The test report is valid for above tested sample only and shall not be reproduced in part without written approval of the laboratory.

Prepared by (Test Engineer):

Joan Wang

Approved (Manager)

Amy Jiang



## 1. GENERAL INFORMATION

### 1.1. Description of Device (EUT)

EUT : Cable Cutting and Stripping Machine

Model : TR-880H

Supplementary Model : See page 2

Rating : AC 110-220V, 50/60Hz

Applicant : Dongguan Turing Automation Technology Co., Ltd  
Address : 7th Floor, Building C, Beitang Industrial Park, No. 80, Tangxia Section, Qingzhang Road, Tangxia Town, Dongguan City, Guangdong Province, China, 523710

Manufacturer : Turing  
Address : 7th Floor, Building C, Beitang Industrial Park, No. 80, Tangxia Section, Qingzhang Road, Tangxia Town, Dongguan City, Guangdong Province, China, 523710

### 1.2. Test Standards

| Test Standards                 |                                                                                                                                                                                                                                                          |
|--------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| EN IEC 61000-6-3: 2021         | Emission standard for residential, commercial and light-industrial environments                                                                                                                                                                          |
| EN IEC 61000-6-1: 2019         | Immunity for residential, commercial and light-industrial environments                                                                                                                                                                                   |
| EN IEC 61000-3-2: 2019+A1:2021 | Electromagnetic compatibility(EMC)-Part 3-2:Limits-Limits for harmonic current emissions(equipment input current $\leq 16A$ per phase)                                                                                                                   |
| EN 61000-3-3: 2013+A2:2021     | Electromagnetic compatibility(EMC)-Part 3-3:Limits-Limitation of voltage changes, Voltage fluctuations and flicker in public low-voltage supply systems. For equipment with Rated current $\leq 16A$ per phase and not subject to conditional connection |

### 1.3. Test Summary

For the EUT described above.

Table 1: Tests Carried Out Under EN IEC 61000-6-3: 2021

| Standard               | Test Items                                                   | Status |
|------------------------|--------------------------------------------------------------|--------|
| EN IEC 61000-6-3: 2021 | Disturbance Voltage at The Mains Terminals (150KHz To 30MHz) | √      |
|                        | Radiated Disturbances (30MHz To 1000MHz)                     | √      |

√ Indicates that the test is applicable

× Indicates that the test is not applicable

Table 2: Tests Carried Out Under EN IEC 61000-6-1: 2019

| Standard                             | Test Items                                         | Status |
|--------------------------------------|----------------------------------------------------|--------|
| EN61000-4-2:2009                     | Electrostatic discharge Immunity                   | √      |
| EN61000-4-3:2006<br>+A1:2008+A2:2010 | Radiated Susceptibility (80MHz to 1GHz)            | √      |
| EN61000-4-4:2004+A1:2010             | Electrostatic Fast Transient/Burst Immunity        | √      |
| EN61000-4-5:2006                     | Surge Immunity                                     | √      |
| EN61000-4-6:2009                     | Conducted Susceptibility (150KHz to 80MHz)         | √      |
| EN61000-4-8:2010                     | Power Frequency Magnetic Field Immunity (12.4.5KW) | √      |
| EN61000-4-11:2004                    | Voltage Dips Short Interruptions Immunity Tests    | √      |

√ Indicates that the test is applicable

√ Indicates that the test is not applicable

Table 3: Tests Carried Out Under EN IEC 61000-3-2: 2019+A1:2021& EN 61000-3-3:2013

| Standard                       | Test Items           | Status |
|--------------------------------|----------------------|--------|
| EN IEC 61000-3-2: 2019+A1:2021 | Harmonic Current     | √      |
| EN 61000-3-3: 2013+A2:2021     | Voltage Fluctuations | √      |

√ Indicates that the test is applicable

√ Indicates that the test is not applicable

#### 1.4. Test Methodology

All measurements contained in this report were conducted with CISPR 16-1: 2002, radio disturbance and immunity measuring apparatus, and CISPR16-2, Method of measurement of disturbances and immunity.

All measurement required was performed at laboratory of Shenzhen Huaxiang Testing Co., Ltd.,

#### 1.5. Test Facility

The test facility is recognized, certified, or accredited by the following organizations:

EMC Laboratory has been registered and fully described in a report filed with the (FCC)

Federal Communications Commission. The acceptance letter from the FCC is maintained in our files Registration 222278.

The facility also complies with the radiated and AC line conducted test site criteria set forth in CISPR 16-1, CISPR16-2.

#### 1.6. Measurement Uncertainty

Radiation Uncertainty :  $U_r = \pm 3.84\text{dB}$

Conduction Uncertainty :  $U_c = \pm 2.72\text{dB}$

## 2. MEASURING DEVICE AND TEST EQUIPMENT

### 2.1. For Power Line Conducted Emission

| Item | Equipment     | Manufacturer    | Model No.              | Serial No.                | Last Cal.     | Cal. Interval |
|------|---------------|-----------------|------------------------|---------------------------|---------------|---------------|
| 1.   | Test Receiver | Rohde & Schwarz | ESCI EMI TEST RECEIVER | ID:1166.5950K03-101431-Jq | Nov. 20, 2023 | 1 Year        |
| 2.   | L.I.S.N.      | Rohde & Schwarz | ESH3-Z5                | 831.5518.52               | Nov. 20, 2023 | 1 Year        |
| 3.   | Pulse Limiter | SCHWARZ BECK    | VTSD 9561-F            | 9561-G071                 | Nov. 20, 2023 | 1 Year        |

### 2.2. For Radiated Emission Measurement

| Item | Equipment         | Manufacturer    | Model No.          | Serial No.                | Last Cal.     | Cal. Interval |
|------|-------------------|-----------------|--------------------|---------------------------|---------------|---------------|
| 1.   | Spectrum Analyzer | Agilent         | E4408B             | CFG006                    | Nov. 20, 2023 | 1 Year        |
| 2.   | Test Receiver     | Rohde & Schwarz | ESPI TEST RECEIVER | ID:1164.6607K03-102109-MH | Nov. 20, 2023 | 1 Year        |
| 3.   | Bilog Antenna     | Sunol Sciences  | Model JB6 Antenna  | A090414                   | Nov. 20, 2023 | 1 Year        |
| 4.   | 50 Coaxial Switch | Anritsu Corp    | MP59B              | 6100237248                | /             | /             |
| 5.   | Horn Ant          | Schwarzbeck     | Model DRH-118      | A091114                   | Nov. 20, 2023 | 1 Year        |

### 2.3. For Harmonic Current / Flicker Measurement

| Item | Equipment                | Manufacturer | Model No.     | Serial No. | Last Cal.     | Cal. Interval |
|------|--------------------------|--------------|---------------|------------|---------------|---------------|
| 1.   | Signal Conditioning Unit | SCHAFFNER    | CCN1000-1     | 72314      | Nov. 20, 2023 | 1 Year        |
| 2.   | Power Supply             | SCHAFFNER    | NSG1007-3-240 | 56110      | Nov. 20, 2023 | 1 Year        |

### 2.4. For Electrostatic Discharge Immunity Test

| Item | Equipment  | Manufacturer | Model No. | Serial No. | Last Cal.     | Cal. Interval |
|------|------------|--------------|-----------|------------|---------------|---------------|
| 1.   | ESD Tester | PRIMA        | ESD6100   | 144305     | Nov. 20, 2023 | 1 Year        |

## 2.5.For Electrical Fast Transient /Burst Immunity Test

| Item | Equipment      | Manufacturer | Model No.       | Serial No. | Last Cal.     | Cal. Interval |
|------|----------------|--------------|-----------------|------------|---------------|---------------|
| 1.   | Burst Tester   | HTEC         | HETR-880H<br>51 | 144303     | Nov. 20, 2023 | 1 Year        |
| 2.   | Coupling Clamp | HAEFELY      | IP-4A           | 147147     | /             | /             |

## 2.6.For Surge Immunity Test

| Item | Equipment    | Manufacturer | Model No. | Serial No. | Last Cal.     | Cal. Interval |
|------|--------------|--------------|-----------|------------|---------------|---------------|
| 1.   | Surge Tester | HTEC         | HCWG      | 144302     | Nov. 20, 2023 | 1 Year        |

## 2.7.For Injected Current Susceptibility Test

| Item | Equipment  | Manufacturer | Model No.  | Serial No. | Last Cal.     | Cal. Interval |
|------|------------|--------------|------------|------------|---------------|---------------|
| 1.   | Simulator  | SCHAFFNER    | NSG2070    | 1086       | Nov. 20, 2023 | 1 Year        |
| 2.   | CDN        | SCHAFFNER    | M016       | 20812      | Nov. 20, 2023 | 1 Year        |
| 3.   | CDN        | SCHAFFNER    | M016       | 20812      | Nov. 20, 2023 | 1 Year        |
| 4.   | Attenuator | SCHAFFNER    | INA 2070-1 | 2086       | Nov. 20, 2023 | 1 Year        |

## 2.8.For Magnetic Field Immunity Test


| Item | Equipment                | Manufacturer | Model No. | Serial No. | Last Cal.     | Cal. Interval |
|------|--------------------------|--------------|-----------|------------|---------------|---------------|
| 1.   | Magnetic Field<br>Tester | HTEC         | HPFM T    | 144301     | Nov. 20, 2023 | 1 Year        |

## 2.9.For Voltage Dips and Interruptions Test

| Item | Equipment   | Manufacturer | Model No. | Serial No. | Last Cal.     | Cal. Interval |
|------|-------------|--------------|-----------|------------|---------------|---------------|
| 1.   | Dips Tester | HTEC         | HPFS      | 144304     | Nov. 20, 2023 | 1 Year        |

### 3. POWER LINE CONDUCTED EMISSION MEASUREMENT

#### 3.1. Block Diagram of Test Setup



#### 3.2. Measuring Standard

EN IEC 61000-6-3: 2021

Power Line Conducted Emission Limits (Class B)

| Frequency<br>(MHz)                                                                                      | Limit (dBμV)     |               |
|---------------------------------------------------------------------------------------------------------|------------------|---------------|
|                                                                                                         | Quasi-peak Level | Average Level |
| 0.15 ~ 0.50                                                                                             | 66.0 ~ 56.0 *    | 56.0 ~ 46.0 * |
| 0.50 ~ 5.00                                                                                             | 56.0             | 46.0          |
| 5.00 ~ 30.00                                                                                            | 60.0             | 50.0          |
| NOTE1-The lower limit shall apply at the transition frequencies.                                        |                  |               |
| NOTE2-The limit decreases linearly with the logarithm of the frequency in the range 0.15MHz to 0.50MHz. |                  |               |

#### 3.3. EUT Configuration on Measurement

The following equipments are installed on Conducted Emission Measurement to meet EN61000-6-3 requirements and operating in a manner which tends to maximize its emission characteristics in a normal application.

EUT : Cable Cutting and Stripping Machine  
 Model Number : TR-880H  
 Serial Number : N/A

### 3.4. Operating Condition of EUT

3.4.1. Setup the EUT as shown on Section 3.1.

3.4.2. Turn on the power of all equipments.

3.4.3. Let the EUT work in measuring mode (On) and measure it.

### 3.5. Test Procedure

The EUT is put on the plane 0.8m high above the ground by insulating support and connected to the AC mains through Line Impedance Stability Network (L.I.S.N). This provided a 50ohm coupling impedance for the tested equipments. Both sides of AC line are investigated to find out the maximum conducted emission according to the EN61000-6-3 regulations during conducted emission measurement.

The bandwidth of the field strength meter (R&S Test Receiver ESCI 3) is set at 9KHz in 150KHz~30MHz and 200Hz in 9KHz~150KHz.

The frequency range from 150kHz to 30MHz is investigated


### 3.6. Measuring Results

PASS

Please reference to the following pages.

## Conducted Emission Test Data


EUT : Cable Cutting and Stripping Machine Model : TR-880H  
Operating Condition : Normal Working Test Site: : Shielded Room  
Power Supply : AC 110-220V, 50/60Hz Phase : L-line  
Operator: : Mark Tem : 24℃ Hum:55%  
Start of Test: : 2024-06-28



| No. | Mk. | Freq.  | Reading | Correct | Measure- | Limit | Over   |          |         |
|-----|-----|--------|---------|---------|----------|-------|--------|----------|---------|
|     |     | MHz    | Level   | Factor  | ment     |       |        | Detector | Comment |
|     |     |        | dBuV    | dB      | dBuV     | dBuV  | dB     |          |         |
| 1   |     | 0.1683 | 46.11   | 0.00    | 46.11    | 65.04 | -18.93 | QP       |         |
| 2   |     | 0.1683 | 25.48   | 0.00    | 25.48    | 55.04 | -29.56 | AVG      |         |
| 3   |     | 0.2117 | 47.60   | 0.00    | 47.60    | 63.13 | -15.53 | QP       |         |
| 4   |     | 0.2117 | 28.74   | 0.00    | 28.74    | 53.13 | -24.39 | AVG      |         |
| 5   |     | 0.2573 | 39.66   | 0.00    | 39.66    | 61.52 | -21.86 | QP       |         |
| 6   |     | 0.2573 | 22.04   | 0.00    | 22.04    | 51.52 | -29.48 | AVG      |         |
| 7   |     | 0.3266 | 39.06   | 0.00    | 39.06    | 59.54 | -20.48 | QP       |         |
| 8   |     | 0.3266 | 21.19   | 0.00    | 21.19    | 49.54 | -28.35 | AVG      |         |
| 9   |     | 0.4080 | 35.77   | 0.00    | 35.77    | 57.69 | -21.92 | QP       |         |
| 10  |     | 0.4080 | 17.85   | 0.00    | 17.85    | 47.69 | -29.84 | AVG      |         |
| 11  | *   | 0.5347 | 42.59   | 0.00    | 42.59    | 56.00 | -13.41 | QP       |         |
| 12  |     | 0.5347 | 25.26   | 0.00    | 25.26    | 46.00 | -20.74 | AVG      |         |

## Conducted Emission Test Data

EUT : Cable Cutting and Stripping Machine Model : TR-880H  
Operating Condition : Normal Working Test Site: : Shielded Room  
Power Supply : AC 110-220V, 50/60Hz, Phase : N-line  
Operator: : Mark Tem : 24℃ Hum:55%  
Start of Test: : 2024-06-28




| No. | Mk. | Freq.<br>MHz | Reading<br>Level<br>dBμV | Correct<br>Factor<br>dB | Measure-<br>ment<br>dBμV | Limit<br>dBμV | Over<br>dB | Detector | Comment |
|-----|-----|--------------|--------------------------|-------------------------|--------------------------|---------------|------------|----------|---------|
| 1   |     | 0.1554       | 45.04                    | 0.00                    | 45.04                    | 65.70         | -20.66     | QP       |         |
| 2   |     | 0.1554       | 19.01                    | 0.00                    | 19.01                    | 55.70         | -36.69     | AVG      |         |
| 3   |     | 0.2346       | 40.28                    | 0.00                    | 40.28                    | 62.28         | -22.00     | QP       |         |
| 4   |     | 0.2346       | 17.35                    | 0.00                    | 17.35                    | 52.28         | -34.93     | AVG      |         |
| 5   |     | 0.2648       | 39.66                    | 0.00                    | 39.66                    | 61.28         | -21.62     | QP       |         |
| 6   |     | 0.2648       | 18.10                    | 0.00                    | 18.10                    | 51.28         | -33.18     | AVG      |         |
| 7   |     | 0.3243       | 39.71                    | 0.00                    | 39.71                    | 59.59         | -19.88     | QP       |         |
| 8   |     | 0.3243       | 24.57                    | 0.00                    | 24.57                    | 49.59         | -25.02     | AVG      |         |
| 9   |     | 0.5345       | 33.09                    | 0.00                    | 33.09                    | 56.00         | -22.91     | QP       |         |
| 10  |     | 0.5345       | 13.52                    | 0.00                    | 13.52                    | 46.00         | -32.48     | AVG      |         |
| 11  | *   | 0.9545       | 44.93                    | 0.00                    | 44.93                    | 56.00         | -11.07     | QP       |         |
| 12  |     | 0.9545       | 29.87                    | 0.00                    | 29.87                    | 46.00         | -16.13     | AVG      |         |

## 4. RADIATED EMISSION MEASUREMENT

### 4.1. Block Diagram of Test

#### 4.1.1. Block diagram of test setup (In chamber)



### 4.2. Measuring Standard

EN IEC 61000-6-3: 2021

### 4.3. Radiated Emission Limits

All emanations from a class B device or system, including any network of conductors and apparatus connected thereto, shall not exceed the level of field strengths specified below:

| FREQUENCY<br>(MHz) | DISTANCE<br>(Meters) | FIELD STRENGTHS LIMIT<br>(dB $\mu$ V/m) |
|--------------------|----------------------|-----------------------------------------|
| 30 ~ 230           | 3                    | 40                                      |
| 230 ~ 1000         | 3                    | 47                                      |

Note: (1) The smaller limit shall apply at the combination point between two frequency bands.

(2) Distance refers to the distance in meters between the measuring instrument antenna and the closed point of any part of the EUT.

### 4.4. EUT Configuration on Test

The EN61000-6-3 regulations test method must be used to find the maximum emission during radiated emission measurement.

#### 4.5. Operating Condition of EUT

4.5.1. Turn on the power.

4.5.2. After that, let the EUT work in test mode (Normal) and measure it.

#### 4.6. Test Procedure

The EUT is placed on a turn table which is 0.8 meter high above the ground. The turn table can rotate 360 degrees to determine the position of the maximum emission level. The EUT is set 3 meters away from the receiving antenna which is mounted on an antenna tower. The antenna can be moved up and down from 1 to 4 meters to find out the maximum emission level. Bilog antenna (calibrated by Dipole Antenna) is used as a receiving antenna. Both horizontal and vertical polarization of the antenna are set on test.

The bandwidth of the Receiver (ESCI 3) is set at 120kHz.

The frequency range from 30MHz to 1000MHz is investigated.


#### 4.7. Measuring Results

PASS

Please reference to the following pages

## Radiated Emission Test Data

EUT : Cable Cutting and Stripping Machine Model : TR-880H  
Operating Condition : Normal Working Test Site: : Shielded Room  
Power Supply : AC 110-220V, 50/60Hz, Polarization : Horizontal  
Operator: : Mark Tem : 24°C Hum:55%  
Start of Test: : 2024-06-28



| No. | Mk. | Freq.    | Reading Level | Correct Factor | Measurement | Limit  | Over   | Antenna Height | Table Degree |         |
|-----|-----|----------|---------------|----------------|-------------|--------|--------|----------------|--------------|---------|
|     |     | MHz      | dBuV          | dB/m           | dBuV/m      | dBuV/m | dB     | cm             | degree       | Comment |
| 1   | *   | 30.7455  | 13.94         | 19.92          | 33.86       | 40.00  | -6.14  | peak           |              |         |
| 2   |     | 122.4040 | 12.88         | 13.80          | 26.68       | 40.00  | -13.32 | peak           |              |         |
| 3   |     | 160.9089 | 13.62         | 13.05          | 26.67       | 40.00  | -13.33 | peak           |              |         |

## Radiated Emission Test Data


EUT : Cable Cutting and Stripping Machine Model : TR-880H  
 Operating Condition : Normal Working Test Site: : Shielded Room  
 Power Supply : AC 110-220V, 50/60Hz, Polarization: : Vertical  
 Operator: : Mark Tem : 24°C Hum:55%  
 Start of Test: : 2024-06-28



| No. | Mk. | Freq.    | Reading Level | Correct Factor | Measurement | Limit  | Over  | Antenna Height | Table Degree |         |
|-----|-----|----------|---------------|----------------|-------------|--------|-------|----------------|--------------|---------|
|     |     | MHz      | dBuV          | dB/m           | dBuV/m      | dBuV/m | dB    | cm             | degree       | Comment |
| 1   | *   | 30.3173  | 12.58         | 21.65          | 34.23       | 40.00  | -5.77 | QP             |              |         |
| 2   |     | 51.4807  | 23.79         | 8.37           | 32.16       | 40.00  | -7.84 | peak           |              |         |
| 3   |     | 142.8243 | 17.36         | 12.94          | 30.30       | 40.00  | -9.70 | peak           |              |         |

## 5. HARMONIC CURRENT EMISSION MEASUREMENT

### 5.1. Block Diagram of Test Setup



### 5.2. Measuring Standard

EN IEC 61000-3-2: 2019+A1:2021

### 5.3. Operation Condition of EUT


Same as Section 3.4, except the test setup replaced as Section 5.1.

### 5.4. Measuring Results

N/A

## 6. VOLTAGE FLUCTUATION AND FLICKER MEASUREMENT

### 6.1. Block Diagram of Test Setup



### 6.2. Measuring Standard

EN 61000-3-3: 2013+A2:2021

### 6.3. Operation Condition of EUT

6.3.1. Setup the EUT and simulators as shown in Section 6.1.

6.3.2. Turn on the power of all equipments.

6.3.3. Let the EUT work in test modes (Normal) and test it.

### 6.4. Measuring Results

PASS

Please reference to the following page

EN 61000-3-3 TEST REPORT 2024-06-28 15:23

Unit: Cable Cutting and Stripping Machine M/N: TR-880H  
Test mode: Normal Working

Manufacturer: Dongguan Turing Automation Technology Co., Ltd

Operator: Mark

### TEST SETUP

Test Freq.: 50.00 Hz. Test Voltage: 230.0 vac  
Waveform: SINE  
Test Time: 120.0 min. Tshort: 10.0 min.

Prog. Zo Enabled: YES Prog. Zo: 0.000

Voltage Change less than once per Hour: NO  
Impedance selected: IEC-725 STD. REF.

Synthetic R+L Enabled: NO  
Resistance: 0.380 Ohms Inductance: 460.000 uH

### TEST DATA


| Result:   | PASS  | EUT Data | Limit | Result | Test Enabled |
|-----------|-------|----------|-------|--------|--------------|
| Pst max   | 0.170 | 1.00     | PASS  | true   |              |
| Plt max   | 0.152 | 0.65     | PASS  | true   |              |
| dc %      | 0.00  | 3.00     | PASS  | true   |              |
| dmax %    | 1.21  | 4.00     | PASS  | true   |              |
| d(t) sec. | 0.00  | 0.20     | PASS  | true   |              |

| Power Source Data |       |       |           |
|-------------------|-------|-------|-----------|
| Source Pst max    | 0.231 | 0.400 | PASS true |
| % THD             | 0.03  | 3.00  | PASS true |


## 7. ELECTROSTATIC DISCHARGE IMMUNITY TEST

### 7.1. Block Diagram of Test Setup

#### 7.1.1. Block Diagram of the EUT and the simulators



#### 7.1.2. Block diagram of ESD test setup



### 7.2. Test Standard

EN IEC 61000-6-1: 2019(EN61000-4-2: 2009)

Severity Level: 3 / Air Discharge:  $\pm 8\text{KV}$  Level: 2 / Contact Discharge:  $\pm 4\text{KV}$

### 7.3. Severity Levels and Performance Criterion

#### 7.3.1. Severity level

| Level | Test Voltage<br>Contact Discharge (KV) | Test Voltage<br>Air Discharge (KV) |
|-------|----------------------------------------|------------------------------------|
| 1     | $\pm 2$                                | $\pm 2$                            |
| 2     | $\pm 4$                                | $\pm 4$                            |
| 3     | $\pm 6$                                | $\pm 8$                            |
| 4     | $\pm 8$                                | $\pm 15$                           |
| X     | Special                                | Special                            |

#### 7.3.2. Performance criterion: B

### 7.4. EUT Configuration

The configuration of EUT is listed in Section 3.3.

## 7.5. Operating Condition of EUT

Same as conducted emission measurement, which is listed in Section 3.4. Except the test set up replaced by Section 7.1.

## 7.6. Test Procedure

### 7.6.1. Air Discharge:

This test is done on a non-conductive surface. The round discharge tip of the discharge electrode shall be approached as fast as possible to touch the EUT. After each discharge, the discharge electrode shall be removed from the EUT. The generator is then re-triggered for a new single discharge and repeated 10 times for each pre-selected test point. This procedure shall be repeated until all the air discharge completed.

### 7.6.2. Contact Discharge:

All the procedure shall be same as Section 7.6.1. except that the tip of the discharge electrode shall touch the EUT before the discharge switch is operated.

### 7.6.3. Indirect discharge for horizontal coupling plane

At least 10 single discharges (in the most sensitive polarity) shall be applied at the front edge of each HCP opposite the center point of each unit (if applicable) of the EUT and 0.1m from the front of the EUT. The long axis of the discharge electrode shall be in the plane of the HCP and perpendicular to its front edge during the discharge.

### 7.6.4. Indirect discharge for vertical coupling plane

At least 10 single discharge (in the most sensitive polarity) shall be applied to the center of one vertical edge of the coupling plane. The coupling plane, of dimensions 0.5m X 0.5m, is placed parallel to, and positioned at a distance of 0.1m from the EUT. Discharges shall be applied to the coupling plane, with this plane in sufficient different positions that the four faces of the EUT are completely illuminated.

## 7.7. Test Results

PASS

Please refer to the following page

## Electrostatic Discharge Test Result

|                   |                                                                                     |               |              |
|-------------------|-------------------------------------------------------------------------------------|---------------|--------------|
| Applicant         | : Dongguan Turing Automation Technology Co., Ltd                                    | Test Date     | : 2024-06-28 |
| EUT               | : Cable Cutting and Stripping Machine                                               | Temperature   | : 22℃        |
| M/N               | : TR-880H                                                                           | Humidity      | : 50%        |
| Power Supply      | : AC 110-220V, 50/60Hz,                                                             | Test Mode     | : Full load  |
| Air discharge     | : $\pm 2.0\text{KV}$ , $\pm 4.0\text{KV}$ , $\pm 6.0\text{KV}$ , $\pm 8.0\text{KV}$ | Criterion     | : B          |
| Contact discharge | : $\pm 2.0\text{KV}$ , $\pm 4.0\text{KV}$                                           | Test Engineer | : Mark       |

## Air Discharge

| Test Points | Test Levels                         |                                     |                                     | Results                             |                          |                                                                  |
|-------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|--------------------------|------------------------------------------------------------------|
|             | $\pm 2\text{kV}$                    | $\pm 4\text{kV}$                    | $\pm 8\text{kV}$                    | Passed                              | Fail                     | Performance Criterion                                            |
| Front       | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Back        | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Left        | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Right       | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Top         | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Bottom      | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |

## Contact Discharge

| Test Points | Test Levels                         |                                     |                          | Results                             |                          |                                                                  |
|-------------|-------------------------------------|-------------------------------------|--------------------------|-------------------------------------|--------------------------|------------------------------------------------------------------|
|             | $\pm 2\text{ kV}$                   | $\pm 4\text{ kV}$                   | $\pm 6\text{ kV}$        | Passed                              | Fail                     | Performance Criterion                                            |
| Front       | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Back        | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Left        | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Right       | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Top         | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Bottom      | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |

## Discharge To Horizontal Coupling Plane

| Side of EUT | Test Levels                         |                                     |                          | Results                             |                          |                                                                  |
|-------------|-------------------------------------|-------------------------------------|--------------------------|-------------------------------------|--------------------------|------------------------------------------------------------------|
|             | $\pm 2\text{ kV}$                   | $\pm 4\text{ kV}$                   | $\pm 6\text{ kV}$        | Passed                              | Fail                     | Performance Criterion                                            |
| Front       | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Back        | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Left        | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Right       | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |

## Discharge To Vertical Coupling Plane

| Side of EUT | Test Levels                         |                                     |                          | Results                             |                          |                                                                  |
|-------------|-------------------------------------|-------------------------------------|--------------------------|-------------------------------------|--------------------------|------------------------------------------------------------------|
|             | $\pm 2\text{ kV}$                   | $\pm 4\text{ kV}$                   | $\pm 6\text{ kV}$        | Passed                              | Fail                     | Performance Criterion                                            |
| Front       | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Back        | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Left        | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Right       | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |


## 8. RF FIELD STRENGTH SUSCEPTIBILITY TEST

### 8.1. Block Diagram of Test

#### 8.1.1. Block diagram of connection between the EUT and Load



#### 8.1.2. Block diagram of RS test setup



### 8.2. Test Standard

EN IEC 61000-6-1: 2019(EN61000-4-3:2006 +A1:2008+A2:2010 (Severity Level: 2, 3V / m)

### 8.3. Severity Levels and Performance Criterion

#### 8.1.3. Severity Levels

| Level | Field Strength V/m |
|-------|--------------------|
| 1     | 1                  |
| 2     | 3                  |
| 3     | 10                 |
| X     | Special            |

#### 8.1.4. Performance Criterion : A

### 8.4. EUT Configuration on Test

The configuration of the EUT is same as Section 3.3.

### 8.5. Operating Condition of EUT

Same as radiated emission measurement which is listed in Section 3.4, except the test setup replaced as Section 8.1.

### 8.6. Test Procedure

The EUT are placed on a table which is 0.8 meter high above the ground. The

EUT is set 3 meters away from the transmitting antenna which is mounted on an antenna tower. Both horizontal and vertical polarization of the antenna are set on test. Each of the four sides of the EUT must be faced this transmitting antenna and measured individually.

In order to judge the EUT performance, a CCD camera is used to monitor its screen.

All the scanning conditions are as following:

| Condition of Test         | Remark                  |
|---------------------------|-------------------------|
| 1. Fielded Strength       | 3V/m (Severity Level 2) |
| 2. Radiated Signal        | Modulated               |
| 3. Scanning Frequency     | 80-1000MHz              |
| 4. Sweep time of radiated | 0.0015 Decade/s         |
| 5. Dwell Time             | 1 Sec.                  |

### 8.7. Test Results

PASS

Please refer to the following page.

## RF Field Strength Susceptibility Test Results

|                                                                                                                                                                                                  |                                                  |                                    |                                                 |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------|------------------------------------|-------------------------------------------------|
| Applicant                                                                                                                                                                                        | : Dongguan Turing Automation Technology Co., Ltd | Test Date                          | : 2024-06-28                                    |
| EUT                                                                                                                                                                                              | : Cable Cutting and Stripping Machine            | Temperature                        | : 22℃                                           |
| M/N                                                                                                                                                                                              | : TR-880H                                        | Humidity                           | : 50 %                                          |
| Field Strength                                                                                                                                                                                   | : 3 V/m                                          | Criterion                          | : A                                             |
| Power Supply                                                                                                                                                                                     | : AC 110-220V, 50/60Hz,                          | Test Mode                          | : Normal                                        |
| Test Engineer                                                                                                                                                                                    | : Mark                                           | Frequency Range                    | : 80 MHz to 1000 MHz                            |
| Modulation:                                                                                                                                                                                      |                                                  | <input type="checkbox"/> None      | <input type="checkbox"/> Pulse                  |
|                                                                                                                                                                                                  |                                                  |                                    | <input checked="" type="checkbox"/> AM 1KHz 80% |
| Frequency Rang 1:<br>80~ 1000MHz                                                                                                                                                                 |                                                  | Frequency Rang 2:<br>1400~ 2000MHz |                                                 |
| Steps                                                                                                                                                                                            | 1                                                | /                                  | %                                               |
|                                                                                                                                                                                                  | Horizontal                                       | Vertical                           | Horizontal                                      |
|                                                                                                                                                                                                  | Vertical                                         |                                    | Vertical                                        |
| Front                                                                                                                                                                                            | PASS                                             | PASS                               | PASS                                            |
| Right                                                                                                                                                                                            | PASS                                             | PASS                               | PASS                                            |
| Rear                                                                                                                                                                                             | PASS                                             | PASS                               | PASS                                            |
| Left                                                                                                                                                                                             | PASS                                             | PASS                               | PASS                                            |
| Test Equipment :<br>1. Signal Generator : 2031 (MARCONI)<br>2. Power Amplifier : 500A100 & 100W/1000M1 (A&R)<br>3. Power Antenna : 3108 (EMCO) & AT1080 (A&R)<br>4. Field Monitor : FM2000 (A&R) |                                                  |                                    |                                                 |
| Note:                                                                                                                                                                                            |                                                  |                                    |                                                 |


## 9. ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST

### 9.1. Block Diagram of Test Setup

#### 9.1.1. Block Diagram of the EUT



#### 9.1.2. EUT Test Setup



### 9.2. Test Standard

EN IEC 61000-6-1: 2019(EN61000-4-4:2004+A1:2010, Severity Level, Level 2: 1KV)

### 9.3. Severity Levels and Performance Criterion

#### 9.3.1. Severity level

| Open Circuit Output Test Voltage $\pm 10\%$ |                       |                                                     |
|---------------------------------------------|-----------------------|-----------------------------------------------------|
| Level                                       | On Power Supply Lines | On I/O (Input/Output) Signal data and control lines |
| 1                                           | 0.5 KV                | 0.25 KV                                             |
| 2                                           | 1 KV                  | 0.5 KV                                              |
| 3                                           | 2 KV                  | 1 KV                                                |
| 4                                           | 4 KV                  | 2 KV                                                |
| X                                           | Special               | Special                                             |

### 9.3.2.Performance criterion : **B**

## 9.4.EUT Configuration

The configuration of EUT is listed in Section 3.3.

## 9.5.Operating Condition of EUT

9.5.1.Setup the EUT as shown in Section 9.1.

9.5.2.Turn on the power of all equipments.

9.5.3.Let the EUT work in test mode (Normal) and measure it.

## 9.6.Test Procedure

The EUT is put on the table which is 0.8 meter high above the ground. This reference ground plane shall project beyond the EUT by at least 0.1m on all sides and the minimum distance between EUT and all other conductive structure, except the ground plane beneath the EUT, shall be more than 0.5m.

### 9.6.1.For input and output AC power ports:

The EUT is connected to the power mains by using a coupling device which couples the ETR-880H interference signal to AC power lines. Both polarities of the test voltage should be applied during compliance test and the duration of the test is 2 mins.

### 9.6.2.For signal lines and control lines ports:

No I/O ports. It's unnecessary to test.

### 9.6.3.For DC output line ports:

It's unnecessary to test.

## 9.7.Test Result

PASS

Please reference to the following page

# Electrical Fast Transient/Burst Test Results

|                                                                                                                                                                                                                                                                     |                                                                                            |                                                                                         |                                                                                   |  |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------|--|
| Standard                                                                                                                                                                                                                                                            | <input type="checkbox"/> IEC 61000-4-4<br><input checked="" type="checkbox"/> EN 61000-4-4 |                                                                                         | Result : <input checked="" type="checkbox"/> PASS / <input type="checkbox"/> FAIL |  |
| Applicant : <u>Dongguan Turing Automation Technology Co., Ltd</u><br>EUT : <u>Cable Cutting and Stripping Machine</u> M/N : <u>TR-880H</u><br>Input Voltage: <u>AC 110-220V, 50/60Hz,</u><br>Criterion : <u>B</u><br>Ambient Condition : <u>20 °C</u> <u>50% RH</u> |                                                                                            |                                                                                         |                                                                                   |  |
| Operation Mode : <u>Normal</u>                                                                                                                                                                                                                                      |                                                                                            |                                                                                         |                                                                                   |  |
| Line : <input checked="" type="checkbox"/> AC Mains                                                                                                                                                                                                                 |                                                                                            | Line : <input type="checkbox"/> Signal line <input checked="" type="checkbox"/> DC line |                                                                                   |  |
| Coupling : <input checked="" type="checkbox"/> Direct                                                                                                                                                                                                               |                                                                                            | Coupling : <input type="checkbox"/> Capacitive                                          |                                                                                   |  |
| Test Time : 120s                                                                                                                                                                                                                                                    |                                                                                            |                                                                                         |                                                                                   |  |
| Line                                                                                                                                                                                                                                                                | Test Voltage                                                                               | Result(+)                                                                               | Result(-)                                                                         |  |
| L                                                                                                                                                                                                                                                                   | 1KV                                                                                        | PASS                                                                                    | PASS                                                                              |  |
| N                                                                                                                                                                                                                                                                   | 1KV                                                                                        | PASS                                                                                    | PASS                                                                              |  |
| PE                                                                                                                                                                                                                                                                  | 1KV                                                                                        | PASS                                                                                    | PASS                                                                              |  |
| L、N                                                                                                                                                                                                                                                                 | 1KV                                                                                        | PASS                                                                                    | PASS                                                                              |  |
| L、PE                                                                                                                                                                                                                                                                | 1KV                                                                                        | PASS                                                                                    | PASS                                                                              |  |
| N、PE                                                                                                                                                                                                                                                                | 1KV                                                                                        | PASS                                                                                    | PASS                                                                              |  |
| L、N、PE                                                                                                                                                                                                                                                              | 1KV                                                                                        | PASS                                                                                    | PASS                                                                              |  |
|                                                                                                                                                                                                                                                                     |                                                                                            |                                                                                         |                                                                                   |  |
|                                                                                                                                                                                                                                                                     |                                                                                            |                                                                                         |                                                                                   |  |
|                                                                                                                                                                                                                                                                     |                                                                                            |                                                                                         |                                                                                   |  |
|                                                                                                                                                                                                                                                                     |                                                                                            |                                                                                         |                                                                                   |  |
| Note:                                                                                                                                                                                                                                                               |                                                                                            |                                                                                         |                                                                                   |  |
| Test Equipment                                                                                                                                                                                                                                                      |                                                                                            | Burst Tester Model : PETR-880H 4010                                                     |                                                                                   |  |


## 10.SURGE IMMUNITY TEST

### 10.1.Block Diagram of Test Setup

#### 10.1.1.Block Diagram of the EUT



#### 10.1.2.Surge Test Setup



### 10.2.Test Standard

EN IEC 61000-6-1: 2019(EN61000-4-5: 2006)

Severity Level: Line to Line: Level 2, 1.0KV

### 10.3.Severity Levels and Performance Criterion

#### 10.3.1.Severity level

| Severity Level | Open-Circuit Test Voltage<br>KV |
|----------------|---------------------------------|
| 1              | 0.5                             |
| 2              | 1.0                             |
| 3              | 2.0                             |
| 4              | 4.0                             |
| *              | Special                         |

#### 10.3.2.Performance criterion : **B**

## 10.4.EUT Configuration

The configuration of EUT is listed in Section 3.3.

## 10.5.Operating Condition of EUT

10.5.1.Setup the EUT as shown in Section 10.1.

10.5.2.Turn on the power of all equipments.

10.5.3.Let the EUT work in test mode (Normal) and measure it.

## 10.6.Test Procedure

10.6.1.Set up the EUT and test generator as shown on Section 10.1.2.

10.6.2.For line to line coupling mode, provide a 1.0 KV 1.2/50us voltage surge  
(at open-circuit condition) and 8/20us current surge to EUT selected points.

10.6.3.At least 5 positive and 5 negative (polarity) tests with a maximum 1/min repetition rate  
are conducted during test.

10.6.4.Different phase angles are done individually.

10.6.5.Record the EUT operating situation during compliance test and decide the EUT  
immunity criterion for above each test.

## 10.7.Test Result

PASS

Please reference to the following page

## Surge Immunity Test Result

| Applicant : <u>Dongguan Turing Automation Technology Co., Ltd</u> |          |             |                 | Test Date : <u>2024-06-28</u>               |        |
|-------------------------------------------------------------------|----------|-------------|-----------------|---------------------------------------------|--------|
| EUT : <u>Cable Cutting and Stripping Machine</u>                  |          |             |                 | Temperature : <u>22℃</u>                    |        |
| M/N : <u>TR-880H</u>                                              |          |             |                 | Humidity : <u>50%</u>                       |        |
| Power Supply : <u>AC 110-220V, 50/60Hz,</u>                       |          |             |                 | Test Mode : <u>Normal</u>                   |        |
| Test Engineer : <u>Mark</u>                                       |          |             |                 | Criterion : <u>B</u>                        |        |
| Location                                                          | Polarity | Phase Angle | Number of Pulse | Pulse Voltage (KV)                          | Result |
| L-N                                                               | +        | 0°          | 5               | 1.0                                         | PASS   |
|                                                                   | +        | 90°         | 5               | 1.0                                         | PASS   |
|                                                                   | +        | 180°        | 5               | 1.0                                         | PASS   |
|                                                                   | +        | 270°        | 5               | 1.0                                         | PASS   |
|                                                                   | -        | 0°          | 5               | 1.0                                         | PASS   |
|                                                                   | -        | 90°         | 5               | 1.0                                         | PASS   |
|                                                                   | -        | 180°        | 5               | 1.0                                         | PASS   |
|                                                                   | -        | 270°        | 5               | 1.0                                         | PASS   |
| L-PE                                                              | +        | 0°          | 5               | 2.0                                         | PASS   |
|                                                                   | +        | 90°         | 5               | 2.0                                         | PASS   |
|                                                                   | +        | 180°        | 5               | 2.0                                         | PASS   |
|                                                                   | +        | 270°        | 5               | 2.0                                         | PASS   |
|                                                                   | -        | 0°          | 5               | 2.0                                         | PASS   |
|                                                                   | -        | 90°         | 5               | 2.0                                         | PASS   |
|                                                                   | -        | 180°        | 5               | 2.0                                         | PASS   |
|                                                                   | -        | 270°        | 5               | 2.0                                         | PASS   |
| N-PE                                                              | +        | 0°          | 5               | 2.0                                         | PASS   |
|                                                                   | +        | 90°         | 5               | 2.0                                         | PASS   |
|                                                                   | +        | 180°        | 5               | 2.0                                         | PASS   |
|                                                                   | +        | 270°        | 5               | 2.0                                         | PASS   |
|                                                                   | -        | 0°          | 5               | 2.0                                         | PASS   |
|                                                                   | -        | 90°         | 5               | 2.0                                         | PASS   |
|                                                                   | -        | 180°        | 5               | 2.0                                         | PASS   |
|                                                                   | -        | 270°        | 5               | 2.0                                         | PASS   |
|                                                                   |          |             |                 |                                             |        |
|                                                                   |          |             |                 |                                             |        |
|                                                                   |          |             |                 |                                             |        |
| Remark:                                                           |          |             |                 | Test Equipment :<br>Surge Tester P surge4.1 |        |


## 11.INJECTED CURRENTS SUSCEPTIBILITY TEST

### 11.1.Block Diagram of Test Setup

#### 11.1.1.Block Diagram of the EUT



#### 11.1.2.Block Diagram of Test Setup



### 11.2.Test Standard

EN IEC 61000-6-1: 2019 (EN61000-4-6: 2009, Severity Level: Level 2, 3V (rms), (0.15MHz ~ 80MHz)

### 11.3.Severity Levels and Performance Criterion

#### 11.3.1.Severity level

| Level | Field Strength V |
|-------|------------------|
| 1     | 1                |
| 2     | 3                |
| 3     | 10               |
| X     | Special          |

#### 11.3.2. Performance criterion: A

### 11.4. EUT Configuration

The configuration of EUT is listed in Section 3.3.

### 11.5. Operating Condition of EUT

11.5.1. Setup the EUT as shown in Section 11.1.

11.5.2. Turn on the power of all equipments.

11.5.3. Let the EUT work in test mode (Normal) and measure it.

### 11.6. Test Procedure

11.6.1. Set up the EUT, CDN and test generators as shown on Section 11.1.2.

11.6.2. Let the EUT work in test mode and measure it.

11.6.3. The EUT are placed on an insulating support 0.1m high above a ground reference plane.

CDN (coupling and decoupling device) is placed on the ground plane about 0.3m from EUT. Cables between CDN and EUT are as short as possible, and their height above the ground reference plane shall be between 30 and 50 mm (where possible).

11.6.4. The disturbance signal described below is injected to EUT through CDN.

11.6.5. The EUT operates within its operational mode(s) under intended climatic conditions after power on.

11.6.6. The frequency range is swept from 150KHz to 80MHz using 3V signal level, and with the disturbance signal 80% amplitude modulated with a 1KHz sine wave.

11.6.7. The rate of sweep shall not exceed  $1.5 \times 10^{-3}$  decades/s. Where the frequency is swept incrementally, the step size shall not exceed 1% of the start and thereafter 1% of the preceding frequency value.

11.6.8. Recording the EUT operating situation during compliance test and decide the EUT immunity criterion.

### 11.7. Test Results

PASS

Please reference to the following page

# Injected Currents Susceptibility Test Results

|                                                                                                                                                                                                                                                             |                   |                           |                                                                                    |        |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|---------------------------|------------------------------------------------------------------------------------|--------|
| Applicant : <u>Dongguan Turing Automation Technology Co., Ltd</u><br>EUT : <u>Cable Cutting and Stripping Machine</u><br>M/N : <u>TR-880H</u><br>Power Supply : <u>AC 110-220V, 50/60Hz,</u><br>Test Engineer : <u>Mark</u>                                 |                   |                           | Test Date: <u>2024-06-28</u><br>Temperature : <u>22°C</u><br>Humidity : <u>58%</u> |        |
| Test Mode : <u>Normal</u>                                                                                                                                                                                                                                   |                   |                           |                                                                                    |        |
| Frequency Range<br>(MHz)                                                                                                                                                                                                                                    | Injected Position | Strength<br>(Unmodulated) | Criterion                                                                          | Result |
| 0.15 ~ 80                                                                                                                                                                                                                                                   | AC Input          | 3V                        | A                                                                                  | PASS   |
| Test Mode : _____                                                                                                                                                                                                                                           |                   |                           |                                                                                    |        |
| Frequency Range<br>(MHz)                                                                                                                                                                                                                                    | Injected Position | Strength<br>(Unmodulated) | Criterion                                                                          | Result |
|                                                                                                                                                                                                                                                             |                   |                           |                                                                                    |        |
|                                                                                                                                                                                                                                                             |                   |                           |                                                                                    |        |
| Remark : 1. Modulation Signal:1KHz 80% AM<br>Measurement Equipment :<br>Simulator: CWS 500 (SWITZERLAND EMTEST)<br>CDN : <input checked="" type="checkbox"/> CDN-M2 (SWITZERLAND EMTEST)<br><input checked="" type="checkbox"/> CDN-M3 (SWITZERLAND EMTEST) |                   | Note:                     |                                                                                    |        |


## 12.MAGNETIC FIELD SUSCEPTIBILITY TEST

### 12.1.Block Diagram of Test

#### 12.1.1.Block diagram of test setup



#### 12.1.2.Magnetic field test setup



### 12.2.Test Standard

EN IEC 61000-6-1: 2019 (EN61000-4-8: 2010, Severity Level: Level 1, 1A / m)

### 12.3.Severity Levels and Performance Criterion

#### 12.3.1.Severity Levels

| Level | Field Strength A/m |
|-------|--------------------|
| 1     | 1                  |
| 2     | 3                  |
| 3     | 10                 |
| 4     | 30                 |
| 5     | 100                |
| X     | Special            |

#### 12.3.2.Performance Criterion : A

### 12.4.EUT Configuration on Test

The configuration of the EUT is same as Section 3.3.

## 12.5. Test Procedure

The EUT is placed in the middle of a induction coil (1\*1m), under which is a 1\*1\*0.1m (high) table, this small table is also placed on a larger table, 0.8 m above the ground. Both horizontal and vertical polarization of the induction coil are set on test, so that each side of the EUT is affected by the magnetic field. Also can reach the same aim by change the position of the EUT.

## 12.6. Test Results

PASS

Please reference to the following page

## Page 39 of 50


## 13.VOLTAGE DIPS AND INTERRUPTIONS TEST

### 13.1.Block Diagram of Test Setup

#### 13.1.1.Block Diagram of the EUT



#### 13.1.2.Dips Test Setup



### 13.2.Test Standard

EN IEC 61000-6-1: 2019(EN61000-4-11: 2004)

### 13.3.Severity Levels and Performance Criterion

#### 13.3.1.Severity level

| Test Level<br>%UT | Voltage dip and short<br>interruptions<br>%UT | Duration<br>(in period) |
|-------------------|-----------------------------------------------|-------------------------|
| 0                 | 100                                           | 0.5                     |
| 40                | 60                                            | 1                       |
| 70                | 30                                            | 5                       |
|                   |                                               | 10                      |
|                   |                                               | 25                      |
|                   |                                               | 50                      |
|                   |                                               | *                       |

13.3.2.Performance criterion : **B&C**

### 13.4.EUT Configuration

The configuration of EUT is listed in Section 3.3.

### 13.5.Operating Condition of EUT

13.5.1 Setup the EUT as shown in Section 13.1.

13.5.2 Turn on the power of all equipments.

13.5.3 Let the EUT work in test mode (Normal) and measure it.

### 13.6.Test Procedure

13.6.1.Set up the EUT and test generator as shown on Section 13.1.2.

13.6.2.The interruptions is introduced at selected phase angles with specified duration.

13.6.3.Record any degradation of performance.

### 13.7.Test Result

PASS

Please reference to the following page

## Voltage Dips And Interruptions Test Results

| Applicant : <u>Dongguan Turing Automation Technology Co., Ltd</u><br>EUT : <u>Cable Cutting and Stripping Machine</u><br>M/N : <u>TR-880H</u><br>Power Supply : <u>AC 110-220V, 50/60Hz,</u> |                                                        |                       | Test Date : <u>2024-06-28</u><br>Temperature : <u>22°C</u><br>Humidity : <u>50%</u><br>Test Engineer : <u>Mark</u>                                |                            |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------|-----------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|
| Test Mode: <u>Normal</u>                                                                                                                                                                     |                                                        |                       |                                                                                                                                                   |                            |
| Test Level<br>% U <sub>T</sub>                                                                                                                                                               | Voltage Dips & Short Interruptions<br>% U <sub>T</sub> | Duration (in periods) | Criterion<br><input type="checkbox"/> A <input checked="" type="checkbox"/> B<br><input checked="" type="checkbox"/> C <input type="checkbox"/> D | Result<br>P=PASS<br>F=Fail |
| 0                                                                                                                                                                                            | 100                                                    | 250P                  | C                                                                                                                                                 | P                          |
| 70                                                                                                                                                                                           | 30                                                     | 25P                   | C                                                                                                                                                 | P                          |
| 0                                                                                                                                                                                            | 100                                                    | 1P                    | B                                                                                                                                                 | P                          |
| 0                                                                                                                                                                                            | 100                                                    | 0.5P                  | B                                                                                                                                                 | P                          |
| Test Mode :                                                                                                                                                                                  |                                                        |                       |                                                                                                                                                   |                            |
| Test Level<br>% U <sub>T</sub>                                                                                                                                                               | Voltage Dips & Short Interruptions<br>% U <sub>T</sub> | Duration (in periods) | Criterion<br><input type="checkbox"/> A <input type="checkbox"/> B<br><input type="checkbox"/> C <input type="checkbox"/> D                       | Result<br>P=PASS<br>F=FAIL |
|                                                                                                                                                                                              |                                                        |                       |                                                                                                                                                   |                            |
|                                                                                                                                                                                              |                                                        |                       |                                                                                                                                                   |                            |
|                                                                                                                                                                                              |                                                        |                       |                                                                                                                                                   |                            |
| Note:                                                                                                                                                                                        |                                                        |                       |                                                                                                                                                   |                            |

## APPENDIX I

### (Photos of EUT)

**FIGURE**  
**GENERAL APPEARANCE OF EUT**



Figure-1




Figure-2




Figure-3



Figure-4



Figure-5



Figure-6



Figure-7



Figure-8



Figure-9



Figure-10



Figure-11



Figure-12




Figure-13

\*\*\*\*\*THE END OF REPORT\*\*\*\*\*